

**2022-2026 Reconditioning/Reconstruction/Resurfacing/Safety Enhancement - Highway**

\*\*Tentative - Subject to Budget Restrictions/Other Conditions

Project Detail							
Year Scheduled	Highway	From	To	Paser Rating	ADT	Length	Project Notes
						Miles	
2023	CTH V	STH 35	CTH E	6	2000	2.3	Mill/Resurface
2023	CTH K-Bridge	B-55-058		NA	2000	0.1	Widen to North for Bike Ped Path
2023	CTH H	2.8mi West of US 63	US 63	5	250	2.8	Recondition/Widen, 24' HMA 3' Shoulder
2023	CTH J	I-94	70th Avenue	5	350	2.0	Reconstruction/Widen/Int Impr, 24' HMA 3' Shoulder
2023	CTH N	CTH J	CTH T	5	480	2.5	Recondition/Widen, 24' HMA 3' Shoulder
2023	CTH W	Rustic Road #4	Dunn County	5-7	210	1.1	Recondition/Widen/Stabilizer, 24' HMA 3' Shoulder
2023	CTH DD	CTH D	STH 128	4	522	3.3	Mill/Resurface
						11.8	
2024	CTH K	170th Street (N)	CTH T	6	1000	1.5	Reconstruction/Widen, 30' HMA 3' Shoulder
2024	CTH A	McCutcheon Rd			10290	0.2	Round-about
2024	CTH U/A	U.P. Railroad	North 2,600 ft	5	10290	0.5	Mill/3"Resurface
2024	CTH A	McCutcheon Rd	Scotts Rd		10290	1.4	Mill/2" Resurface
2024	CTH O	CTH G	CTH S	5	200	3.1	Recondition/Widen 24' HMA 3' Shoulder
2024	CTH X	Elm Street	145th Ave	5	300	0.6	Recondition/Widen, 24' HMA 3' Shoulder
2024	CTH F	Hudson	Pierce County Line	6	8000	5+	Mill/2"Resurface
2024	CTH E	CTH V	CTH I	7	4500	4.0	Mill/2.5"Resurface
						9.8	
2025	CTH K	140th Street	170th Street (N)	5-6	2000	2.5	Reconstruction/Widen, 30' HMA 3' Shoulder, Path by others
2025	CTH S	US 63	CTH O (N)	5	125	1.4	Pulverize/Pave 3" 24' HMA, 4-5' Shoulder
2025	CTH O	CTH S	STH 64/63	5	300	1.0	Reconstruction/Widen/Stabilize
2025	CTH P	STH 64	CTH Q	6	1000	3.0	Reconstruction/Widen, 30' HMA 3' Shoulder
2025	CTH Q	US 63	CTH P	6	240	5.0	Recondition/Widen, 24' HMA 3' Shoulder
						9.0	
2026	CTH W	CTH M	CTH J	5	180	3.4	Recondition/Widen 24' HMA 3' Shoulder
2026	CTH NN	CTH N	US 12	5	100	3.6	Pulverize/Pave 3" 24' HMA, 3' Shoulder
2026	CTH N	CTH B	STH 128	6	600	4.0	Recondition/Widen 24' HMA 3' Shoulder
2026	CTH X	145th AVE	SANDY CREEK	6	230	2.1	Pulverize/Pave 24' HMA, 3' Shoulder
2026	CTH Q	CTH P	DUNN COUNTY	5	200	2.1	Recondition/Widen 24' HMA 3' Shoulder
2026	CTH YY	US 63	CTH Y	6	150	1.6	Recondition/Widen 24' HMA 3' Shoulder
						11.8	
2027	CTH E	CTH A	STH 65	6	1200	5.7	Reconstruction/Widen, 30' HMA, 2'-3' Shoulder
2027	CTH E	US 63	CTH D	6	900	5.7	Recondition/Widen 30' HMA 3' Shoulder
2027	CTH X	SANDY CREEK	DUNN COUNTY	5	170	2.1	Recondition/Widen 24' HMA 3' Shoulder
2027	CTH M	Star Prairie	Polk County Line	5	2000	1.5	Pulverize/Pave 24' HMA, 3' Shoulder
2027	CTH GG	165th Ave	CTH G	5	400	1.7	Pulverize/Pave 24' HMA, 3' Shoulder
						16.7	
TBD	CTH Y	CTH M	CTH N	6	150	4.5	Recondition/Widen 24' HMA 3' Shoulder
TBD	RR #3	CTH E	STH 128	4	50	3.6	Recondition 22' HMA 2' shoulders
TBD	CTH I	Somerses	50th St.	5	890	4.3	Recondition 22' HMA 2' shoulders
TBD	CTH W	Pierce Co. Line	CTH M	4	35	0.5	Recondition 22' HMA 2' shoulders
TBD	CTH G	240th?	USH 63	6	630	2.8	Recondition 22' HMA 2' shoulders
TBD	CTH NN	Termini (dead end)	CTH N	5	130	2.9	Recondition 22' HMA 2' shoulders
TBD	CTH DD	USH 63	CTH D	6	522	5.6	Recondition 22' HMA 2' shoulders
TBD	CTH E	STH 65	CTH T	6	1000	5.0	Reconstruction/Widen, 30' HMA, 2'-3' Shoulder
TBD	CTH A	CTH E	CTH G	6	6300	4.6	Mill 2" resurface
						26.4	
						135.3	