

2024-2028 Reconditioning/Reconstruction/Resurfacing/Safety Enhancement - Highway

**Tentative - Subject to Budget Restrictions/Other Conditions

*Project to be constructed by contractor via State Letting

Project Detail							
Year Scheduled	Highway	From	To	Paser Rating	ADT	Length	Project Notes
						Miles	
2024	CTH V	STH 35	CTH E	4	2875	2.3	Pulverize and Relay 30 ft. HMA 3"
2024	CTH K*	170th Street (N)	CTH T	6	1000	1.5	Reconstruction/Widen, 30' HMA 2' Shoulder
2024	CTH A*	McCutcheon Rd			10290	0.2	Round-about
2024	CTH U/A	U.P. Railroad	Scotts Rd	5	10290	2.4	Pulverize and relay 4 in. (32 ft. in 2-Lane)
2024	CTH F*	Hudson	Pierce County Line	6	8000	5.0	Mill/2"Resurface
2024	CTH E	CTH V	CTH I	4	4500	4.0	Mill/2"Resurface (32ft. Pavement)
2024	CTH O	CTH G	CTH S	3-4	200	3.1	Recondition/Widen 26' HMA 2' Shoulder
						18.5	
2025	CTH X	Elm Street	145th Ave	5	300	0.6	Recondition/Widen, 26' HMA 2' Shoulder
2025	CTH S	US 63	CTH O (N)	4	125	1.4	Pulverize/Pave 3" 26' HMA, 4-5' Shoulder
2025	CTH P	STH 64	CTH Q	4	1000	3.0	Reconstruction/Widen, 30' HMA 3' Shoulder
2025	CTH Q	US 63	CTH P	4	240	5.0	Recondition/Widen, 26' HMA 2' Shoulder
2025	CTH NN	CTH N	US 12	3	100	3.6	Pulverize/Pave 3" 26' HMA, 2' Shoulder
						12.1	
2026	CTH O	CTH S	STH 64/63	5	300	1.0	Reconstruction/Widen/Stabilize
2026	CTH K	140th Street	170th Street (N)	5-6	2000	2.5	Recondition/Widen, 30' HMA 2' Shoulder, Path by others
2026	CTH W	Pierce County Line	CTH J	5	180	3.9	Recondition/Widen 26' HMA 2' Shoulder
2026	CTH C	CTH CC	CTH H	5	2100	1.7	Pulverize/Pave 3" 34', 3ft. Shoulder
2026	CTH N	CTH B	STH 128	6	600	4.0	Recondition/Widen 26' HMA 2' Shoulder
2026	CTH X	145th AVE	SANDY CREEK	6	230	2.1	Pulverize/Pave 26' HMA, 2' Shoulder
2026	CTH Q	CTH P	DUNN COUNTY	5	200	2.1	Recondition/Widen 26' HMA 2' Shoulder
						13.5	
2027	RR #3	CTH E	STH 128	4	50	3.6	Recondition 22' HMA 2' shoulders
2027	CTH E	CTH A	100th Street	6	1200	2.0	Reconstruction/Widen, 30' HMA, 3' Shoulder
2027	CTH X	SANDY CREEK	DUNN COUNTY	5	170	2.1	Recondition/Widen 26' HMA 2' Shoulder
2027	CTH M	Star Prairie	Polk County Line	5	2000	1.5	Pulverize/Pave 30' HMA, 2' Shoulder
2027	CTH YY	US 63	CTH Y	6	150	1.6	Recondition/Widen 26' HMA 2' Shoulder
2027	CTH GG	165th Ave	CTH G	5	400	1.7	Pulverize/Pave 26' HMA, 2' Shoulder
						8.9	
2028	CTH E	100th Street	STH 65	6	1200	3.1	Reconstruction/Widen, 30' HMA, 3' Shoulder
2028	CTH E	US 63	CTH D	6	900	5.7	Recondition/Widen 30' HMA 3' Shoulder
2028	CTH Y	CTH M	CTH N	6	150	4.5	Recondition/Widen 26' HMA 2' Shoulder
2028	CTH A	CTH E	CTH G	5-6	6300	4.6	Mill 2" resurface
2028	CTH E	STH 65	CTH T	5	1000	5.0	Reconstruction/Widen, 30' HMA, 3' Shoulder
						14.1	